



222 Main Street West, Huntsville, ON P1H 1Y1  
Tel: (705) 789-9647

Fax: (705) 789-3353

Agence de foresterie du parc Algonquin  
222, rue Main ouest, Huntsville, ON P1H 1Y1  
[huntsville.office@algonquinforestry.on.ca](mailto:huntsville.office@algonquinforestry.on.ca)

[www.algonquinforestry.on.ca](http://www.algonquinforestry.on.ca)

18 July 2018

**Invitation to Quote - Aggregate Crushing Granular**

The Algonquin Forestry Authority (AFA) is the Ontario Crown Agency responsible for the sustainable forest management in Algonquin Provincial Park.

The AFA is accepting quotations from established and reputable companies for the crushing and stockpiling of 31,000 metric tonnes of type "M" gravel at four separate locations and 10,000 metric tonnes of type "A" gravel at two separate locations within Algonquin Park. Crushing locations (pits) are listed below.

Companies may submit a quote for each pit or a combined quote to complete the crushing at all locations as per the chart below.

Company Name: \_\_\_\_\_

Location and Volume	Price per Tonne
Pit at km 25 Lake Travers road - 10,000 tonnes "M"	_____
Pit at km 41 Lake Travers Road – 8,000 tonnes "M"	_____
Pit at km 62 Lake Travers Road – 8,000 tonnes "M"	_____
Pit at km 62 Lake Travers Road – 5,000 tonnes "A"	_____
Pit at km 8 Basin Lake Road – 5,000 tonnes "A"	_____
Pit at km 28.5 Shirley Lake road - 5,000 tonnes "M"	_____

Volumes have been calculated to meet our current needs, actual volumes may be adjusted slightly. A site visit is being planned. Contact Evan Dombroskie for the Lake Travers and Basin Lake pits and Martin Laflamme for the Shirley Lake pit for tentative dates.

The successful Contractor will be required to enter into a contract with the AFA to supply all required equipment, personnel and materials. WSIB coverage or personal injury insurance and notification to the Ministry of Labour is required prior to commencing, as well as minimum \$2,000,000 liability insurance with the AFA listed as co-insured.

The Contractor will also be required to abide by the terms of the AFA's Environmental Management System and all other laws and regulations of Ontario pertaining to the performance of the work. All workers must have minimum training in either Surface Miner Program in Pits and Quarries or in Forestry Pits and Road Construction Equipment.

Crushing at these pits must be completed by Nov 15, 2018. Stripping of the pit and subsequent rehabilitation is part of the contract subject to AFA direction.



The AFA must be notified 2 days prior to moving into Algonquin Park to start operations. The Contractor cannot move into the park until given approval by the AFA to ensure all issues and contract obligations have been met. Contravention of these terms may result in a contract penalty of 10% or cancellation of the contract.

Crushing is to be done according to OPSS standards. Sampling of granular material may be done at the discretion of AFA to ensure standards are being met. All costs associated with sampling will be deducted from the total invoice. Quality assurance will be based on the OPSS 314, 1001 and 1010. Granular "M" shall have 95-100% pass through a 16.0 mm sieve and the Granular "A" shall have 95-100% pass through a 19.0 mm sieve. If sampling is necessary, 3 sample lots will be taken for analysis. Lots will be taken when approximately 2000, 5000 and 10,000 tonnes are stockpiled. The Contractor must have a person dedicated to inspecting and removing wood and debris from entering the crusher. Contract conditions include a 10% reduction in contract price may be applied if wood content is greater than 1%.

Stockpiling will be done according to OPSS 1001. Conveyor belt scales is the method of determining volume for this contract however volumes will also be confirmed by an AFA supervisor upon completion of the contract. Scales must meet OPSS standard for accuracy. Stockpiles will be measured for volume and payment made accordingly. Payment will not exceed 5% of the contract volume unless specified by AFA and agreed to by the Contractor. Payment will be made upon completion of the crushing at each pit and acceptance of the invoice. Any changes to the pit boundary must be approved by the AFA supervisor. The Contractor must not block the access road into and through the pit upon completion of the project.

The Contractor may be charged \$450.00 for every calendar day that it goes beyond the scheduled completion date.

**Quotes will be based on price per metric tonne with all costs included, excluding HST. The lowest or any quote will not necessarily be accepted.**

Please direct any questions to Evan Dombroskie at 613-735-0173, ext. 229 or by email at [evan.dombroskie@algonquinforestry.on.ca](mailto:evan.dombroskie@algonquinforestry.on.ca) for the Lake Travers and Basin Lake pits and Martin Laflamme at 613-334-6182 or by email at [martin.laflamme@algonquinforestry.on.ca](mailto:martin.laflamme@algonquinforestry.on.ca) for the Shirley Lake pit.

Quotes must be sent either electronically to [tenders@algonquinforestry.on.ca](mailto:tenders@algonquinforestry.on.ca) or delivered in a sealed envelope marked "Crushing at Lake Travers Road, Basin Lake Road and Shirley Lake Road" to our Pembroke office at: 84 Isabella Street, Unit #7, Pembroke, ON K8A 5S5.

**Quotes must be received no later than 4:00 p.m. local time, Wednesday, August 15, 2018**